

Estimate



Carson Pump, LLC
 P.O. Box 20159
 Carson City, NV. 89721

Date	Estimate #
11/17/2020	2390

NV. Lic #39920A
 CA. Lic #745270

Name / Address
City of Fernley Attn: Clerk's Office 595 Silver Lace Blvd. Fernley, NV. 89408 Steve Henderson

Description	Qty	Project	
		Cost	Total
Mobilization and Demobilization from Carson City to Fernley Well #14	1	1,500.00	1,500.00
Remove 200' of 10" X 1-15/16" turbine pump	200	11.00	2,200.00
Conduct video of well after pump removal	1	1,000.00	1,000.00
Brush 14" X 790' well for, est. 8 hrs. (if required)	8	260.00	2,080.00
Bail debris from well, est. 4 hrs.	4	260.00	1,040.00
Disassemble Fairbanks model 13H, 6 stage bowl assembly, steam clean, check for wear and reassemble *	1	800.00	800.00
Reinstall 200' of 10" turbine pump	200	11.00	2,200.00
Conduct video of well after brushing (if required)	1	900.00	900.00
*Costs do not include any parts if required. Customer to be notified of costs related to any repairs or replacement parts.			
Thank you for considering Carson Pump for this proposal		Subtotal	\$11,720.00
		Sales Tax (7.1%)	\$0.00
		Total	\$11,720.00